


# EMERGENCY LIGHTING UPGRADES FOR SALEM DISTRICT COURT



## SHEET INDEX

COVER SHEET

### ELECTRICAL

E0.1	ELECTRICAL LEGEND, NOTES AND SCHEDULES
ED1.1	ELECTRICAL DEMOLITION BASEMENT PLAN
ED1.2	ELECTRICAL DEMOLITION FIRST FLOOR PLAN
E1.1	ELECTRICAL BASEMENT PLAN
E1.2	ELECTRICAL FIRST FLOOR PLAN

### CODE REQUIREMENTS:

2009 INTERNATIONAL BUILDING CODE (IBC)

35 GEREMONTY DR.  
SALEM, NEW HAMPSHIRE

ISSUED FOR BID / CONST.

SEPTEMBER 20, 2018



THE H.L. TURNER GROUP Inc.

27 LOCKE RD. CONCORD NH 03301 (603) 228-1122  
ARCHITECTS • CONSTRUCTION MANAGERS • ENGINEERS • BUILDING SCIENTISTS

TTG PROJECT NO. 4716



KEY PLAN:

PROJECT TITLE/ ADDRESS:

**EMERGENCY LIGHTING  
UPGRADES**

**TOWN OF SALEM, NH**

**SALEM DISTRICT COURT  
35 GEREMONTY DR  
SALEM, NH**

ISSUE:

**BID SET  
09/20/2018**

PROJ. NO.:	18104	STAMP
SCALE:		
DES. BY:	SWD	JOHN
DRAWN BY:	SWD	15
CHKD BY:	JP	15
ISSUE DATE:	09/20/2018	
REVISIONS		

SHEET TITLE:

**ELECTRICAL  
LEGEND, NOTES  
AND SCHEDULES**

**E0.1**

## GENERAL SPECIFICATIONS

1. CONDITIONS OF THE CONTRACT AND DIVISION 1, GENERAL REQUIREMENTS APPLY TO WORK SHOWN ON THESE DRAWINGS. EXAMINE DRAWINGS AND OTHER SPECIFICATIONS FOR REQUIREMENTS THAT AFFECT WORK SHOWN ON THESE DRAWINGS.

2. PROVIDE ITEMS REFERRED TO IN SINGULAR NUMBER IN CONTRACT DOCUMENTS IN QUANTITIES NECESSARY TO COMPLETE WORK.

3. VISIT SITE AND EXAMINE CONDITIONS UNDER WHICH WORK MUST BE PERFORMED. REPORT ADVERSE CONDITIONS IN WRITING TO ARCHITECT. COMMENCEMENT OF WORK SHALL BE CONSTRUED AS COMPLETE ACCEPTANCE OF EXISTING CONDITIONS INCLUDING PREPARATORY WORK DONE BY OTHERS.

4. PERFORM WORK AND PROVIDE MATERIALS AND EQUIPMENT AS SHOWN ON DRAWINGS. COORDINATE ELECTRICAL WORK WITH WORK SHOWN ON THESE DRAWINGS.

5. GIVE NOTICES, FILE PLANS, OBTAIN PERMITS AND LICENSES, PAY FEES AND BACK CHARGES, AND OBTAIN NECESSARY APPROVALS FROM AUTHORITIES THAT HAVE JURISDICTION.

6. PERFORM WORK AS REQUIRED BY CODES, REGULATIONS AND LAWS OF LOCAL, STATE AND FEDERAL GOVERNMENTS AND OTHER AUTHORITIES WITH LAWFUL JURISDICTION.

7. MATERIAL AND EQUIPMENT SHALL BE UL, NEMA, ANSI, IEEE, ADA & CBM APPROVED FOR INTENDED SERVICE. MATERIAL AND INSTALLATION SHALL MEET REQUIREMENTS OF NATIONAL AND STATE ELECTRICAL CODE.

8. MAINTAIN RECORD DRAWINGS ON SITE. RECORD SET MUST BE COMPLETE, CURRENT AND AVAILABLE FOR INSPECTION WHEN REQUISITIONS FOR PAYMENT ARE SUBMITTED.

9. GUARANTEE WORK IN WRITING FOR ONE (1) YEAR FROM DATE OF FINAL ACCEPTANCE. REPAIR OR REPLACE DEFECTIVE MATERIALS OR INSTALLATION AT NO COST TO OWNER. CORRECT DAMAGE CAUSED IN MAKING NECESSARY REPAIRS AND REPLACEMENTS UNDER GUARANTEE AT NO COST TO OWNER.

10. SUBMIT GUARANTEE TO ARCHITECT BEFORE FINAL PAYMENT. STATEMENT OF GUARANTEE REQUIREMENTS SHALL NOT BE INTERPRETED TO LIMIT OWNER'S RIGHTS UNDER LAW AND THIS CONTRACT.

11. DRAWINGS ARE DIAGRAMMATIC AND INDICATE GENERAL ARRANGEMENT OF SYSTEMS. PROVIDE INFORMATION AND COMPONENTS SHOWN ON RISER DIAGRAMS BUT NOT SHOWN ON PLANS, AND VICE VERSA, AS IF EXPRESSLY REQUIRED ON BOTH.

12. UTILIZE MOLDED CASE CIRCUIT BREAKERS. MINIMUM INTERRUPTING CAPACITY SHALL BE 10,000 AMPS SYMMETRICAL AT 240 VOLTS, AND 14,000 AMPS SYMMETRICAL AT 480 VOLTS.

13. TEMPORARY LIGHT AND POWER SHALL BE PROVIDED ON SITE BY THE ELECTRICAL CONTRACTOR. COST OF ELECTRICITY SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.

14. ADDRESS QUESTIONS REGARDING DRAWINGS TO ARCHITECT IN WRITING BEFORE AWARD OF CONTRACT. OTHERWISE, ARCHITECT INTERPRETATION OF MEANING AND INTENT OF DRAWINGS SHALL BE FINAL.

15. SUBMIT SHOP DRAWINGS AND PRODUCT DATA WITHIN THIRTY (30) DAYS AFTER AWARD OF CONTRACT. CHECK, STAMP AND MARK WITH PROJECT NAMES SUBMITTALS BEFORE TRANSMITTING TO ARCHITECT. INDICATE DEVIATIONS FROM CONTRACT DOCUMENTS. SHOP DRAWINGS SHALL BE PROVIDED FOR ALL EQUIPMENT SHOWN ON THE DRAWINGS. PROVIDE SHOP DRAWINGS ON LIGHTING, PANELBOARDS, CIRCUIT BREAKERS, CONDUIT, WIRING DEVICES, LIGHTING CONTROL DEVICES, CABLE AND CONDUCTORS, FIRE ALARM INCLUDING BATTERY CALCULATIONS, RISER DIAGRAM, EQUIPMENT CUTS AND DISCONNECTS.

16. DEVIATION FROM CONTRACT DOCUMENTS, OR PROPOSED SUBSTITUTION OF MATERIALS OR EQUIPMENT FOR THOSE SPECIFIED, SHALL BE REQUESTED IN SEPARATE LETTER, WHETHER DEVIATIONS ARE DUE TO FIELD CONDITIONS, STANDARD SHOP PRACTICE, OR OTHER CAUSE.

17. SUBSTITUTIONS FOR SCHEDULED LIGHTING EQUIPMENT WILL BE REJECTED UNLESS SUBSTITUTION SUBMITTAL IS RECEIVED WITHIN TEN (10) DAYS AFTER CONTRACT AWARD.

18. ELEVATIONS AND FLOOR PLANS OF ALL ELECTRIC ROOMS, WITH PROPOSED MANUFACTURER'S EQUIPMENT, SHALL BE INCLUDED WITHIN SWITCHGEAR SUBMITTAL. SHOP DRAWINGS WILL NOT BE APPROVED WITHOUT VERIFICATION THAT THE PROPOSED ELECTRICAL EQUIPMENT CAN FIT WITHIN THE LIMITS OF THE ELECTRICAL ROOMS INDICATED ON THE ARCHITECTURAL BACKGROUNDS.

19. SCHEDULE AT LEAST TEN (10) WORKING DAYS, EXCLUSIVE ON TRANSMITTAL TIME FOR SUBMITTAL REVIEW.

20. ALL WIRING SHALL BE RUN CONCEALED UNLESS SPECIFIED OTHERWISE.

21. ALL EQUIPMENT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, RECTILINEAR TO BUILDING STRUCTURE.

22. ALL COMPONENTS SHOWN ON THE RISER DIAGRAMS, BUT NOT ON THE PLAN OR VICE VERSA, SHALL BE INCLUDED AS IF SHOWN ON BOTH.

23. LOCATION OF MECHANICAL EQUIPMENT THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THE MECHANICAL DRAWINGS.

24. ALL RACEWAY RUNNING THROUGH BUILDING EXPANSION JOINTS SHALL BE EQUIPPED WITH EXPANSION FITTINGS.

25. CONDUIT HOMERUNS SHOWN ON THE DRAWING WITH MORE THAN THREE (3) CURRENT CARRYING CONDUCTORS ARE SHOWN DIAGRAMMATICALLY. THE CONTRACTOR SHALL NOT INSTALL MORE THAN THREE (3) CURRENT CARRYING CONDUCTORS IN A RACEWAY UNLESS DONE SO STRICTLY BY THE NATIONAL ELECTRICAL CODE AS AMENDED BY THE STATE.

26. THE ELECTRICAL CONTRACTOR SHALL CONSULT AND COOPERATE WITH CONTRACTORS OF OTHER TRADES TO AVOID ANY INTERFERENCE IN THE INSTALLATION OF THEIR RESPECTIVE EQUIPMENT. CONTRACTOR SHALL REVIEW ALL TRADES' CONTRACT DOCUMENTS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR ELECTRICAL EQUIPMENT. COORDINATE EXACT MOUNTING LOCATIONS WITH THE ARCHITECT.

27. BRANCH CIRCUIT WIRING MAY NOT BE SHOWN GRAPHICALLY ON DRAWINGS AND MAY BE INDICATED BY CIRCUIT NUMBERS BESIDE FIXTURES, DEVICES AND EQUIPMENT. PROVIDE COMPLETE WIRING SYSTEM WHETHER OR NOT INDICATED GRAPHICALLY. PHASE BALANCE ALL PANELBOARDS IN FIELD. CIRCUIT NUMBERS ARE DIAGRAMMATIC, UTILIZE AVAILABLE SPACE OR PROVIDE ADDITIONAL BREAKERS AND PANELBOARDS AS NECESSARY.

28. ALL NEW WIRING SHALL BE TYPE THHN/THWN-2 600V. MINIMUM BRANCH CIRCUIT WIRING SHALL BE NO. 12 AWG SOLID COPPER. BRANCH CIRCUITS LONGER THAN 150 FEET FOR 120 VOLTS SHALL BE AT LEAST NO. 10 AWG FROM PANEL TO LAST OUTLET.

29. ALL NEW EXPOSED INTERIOR WIRING ABOVE 8'-0" NOT EXPOSED TO DAMAGE SHALL BE INSTALLED IN ELECTRIC METALLIC TUBING. ALL WIRING IN CONCRETE SLABS OR EXPOSED IN ROOM BELOW 8'-0" OR EXPOSED TO DAMAGE SHALL BE INSTALLED IN RIGID STEEL CONDUIT. EXTERIOR WIRING SHALL BE IN GALVANIZED RIGID METALLIC CONDUIT.

30. INTERRUPTIONS TO EXISTING ELECTRIC SERVICES AND SYSTEMS SHALL BE AS SHORT AS POSSIBLE AND AT A TIME AND DURATION APPROVED BY THE ARCHITECT OR OWNER. INCLUDE ALL PREMIUM TIME ASSOCIATED WITH INTERRUPTIONS. TWENTY-FOUR (24) HOUR NOTICE IS REQUIRED.

31. ALL GROUNDING SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AS AMENDED BY THE STATE OF NEW HAMPSHIRE.

32. ALL FIREPROOFING FOR ELECTRICAL PENETRATIONS SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR.

33. ALL WIRING (LIGHTING BRANCH CIRCUIT) SHALL BE PLENUM RATED; NO EXCEPTIONS. NON-PLENUM RATED CABLES OF ANY KIND SHALL NOT BE PROVIDED.

34. PROVIDE UL LISTED MOLDABLE PUTTY PADS TO SEAL ANNULAR SPACES/ PENETRATIONS AROUND ALL JUNCTION BOXES.

## GENERAL NOTES

1. REFER TO ARCHITECTURAL PLANS AND ELEVATIONS FOR MOUNTING HEIGHTS AND EXACT LOCATIONS OF ALL DEVICES.

2. ALL FLOOR, MASONRY WALLS AND STRUCTURAL CEILING PENETRATIONS SHALL BE SLEVED.

3. PROVIDE FIRE/MOISTURE SEAL FOR WALL, FLOOR OR CEILING PENETRATIONS.

4. DO NOT LAY CABLES OR RACEWAY ON, OR SUPPORT FROM SUSPENDED CEILING OR PIPING AND DUCTWORK.

5. OUTLET BOXES SHALL BE MOUNTED FLUSH. CONDUIT SHALL BE RUN CONCEALED, WHERE WALLS ARE BLOCK, DEVICES AND WIRING SHALL BE SURFACE MOUNTED. PROVIDE WIREMOLD OR EQUAL TO SURFACE MOUNTED RACEWAY WITH FINISHED BOXES.

6. FLEXIBLE CONDUIT CONNECTIONS SHALL BE A MAXIMUM OF 6'-0".

7. MC TYPE CONDUCTOR WITH INTEGRAL GROUND WIRE MAY BE UTILIZED FOR POWER AND LIGHTING CIRCUITS. MC CABLE SHALL BE UTILIZED ONLY WHERE COMPLETELY CONCEALED.

## LIGHTING NOTES

1. ALL CONDUIT, FIXTURES ARE SHOWN DIAGRAMMATICALLY. EXACT LOCATION AND METHOD OF SUPPORT SHALL BE DETERMINED IN THE FIELD, EXCEPT WHERE SPECIFIC DIMENSIONS AND DETAILS ARE SHOWN.


2. ALL LIGHTING FIXTURE SPACING DIMENSIONS AND MOUNTING HEIGHTS ARE RECOMMENDED LOCATIONS. SLIGHT VARIATIONS WHERE NECESSARY TO AVOID INTERFERENCE SHALL BE DETERMINED IN THE FIELD.

3. WHERE REQUIRED, ADDITIONAL SUPPORT STEEL FOR THE LIGHTING INSTALLATION SHALL BE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. SEISMIC RESTRAINTS SHALL BE INCLUDED AS PER STATE BUILDING CODE.

4. PROVIDE SEPARATE UN-SWITCHED NEUTRAL TO ALL EXIT SIGNS, EMERGENCY BATTERY UNITS AND EMERGENCY LIGHT FIXTURES CONTAINING EMERGENCY BALLASTS.

5. FOR RENOVATION PROJECTS, PROVIDE NEW BRANCH CIRCUITRY BETWEEN ALL NEW FIXTURES BEING PROVIDED, UNLESS NOTED OTHERWISE ON DRAWINGS.

## LIGHTING FIXTURE SYMBOLS



## BRANCH CIRCUIT AND FEEDER SYMBOLS

— Branch circuit or feeder concealed unless otherwise noted. Branch circuit diagonal lines indicate number of conductors, no diagonal lines indicate two (2) conductors (1 phase and 1 neutral). Ground wire(s) not indicated. Minimum size conductor #12 AWG and 3/4" conduit, unless otherwise noted

#1#1#6G-1½" C Indicates (3) #1 AWG (PHASE), (1) #1 AWG (NEUTRAL), (1) #6 GROUND IN A 1-1/2" CONDUIT

— Flexible connection to motor or equipment

PP1-1 20A/1P HOMERUN TO PANELBOARD "P1" CIRCUIT NUMBER 1. DIAGONAL LINES INDICATE (1) PHASE AND (1) NEUTRAL CONDUCTOR. (1) GROUNDING CONDUCTOR UNDERSTOOD.

## DEMOLITION NOTES

1. THE ELECTRICAL DEMOLITION PLANS AND DETAILS INDICATE THE GENERAL INTENT AND ARE NOT INTENDED TO SHOW ALL ITEMS TO BE REMOVED OR REMAINED. THE ELECTRICAL CONTRACTOR SHALL VISIT THE SITE PRIOR TO THE SUBMISSION OF BIDS TO BECOME FAMILIAR WITH THE ACTUAL CONDITIONS AND EXTENT OF WORK, DEVICES AND EQUIPMENT LOCATED ON WALLS AND/OR CEILINGS TO BE REMOVED SHALL BE DISCONNECTED AND MADE SAFE. THE ELECTRICAL CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE OF ANY UNANTICIPATED HIDDEN CONDITIONS ENCOUNTERED DURING DEMOLITION.

2. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF ALL SYSTEMS OR BUILDING COMPONENTS DAMAGED DURING THE EXECUTION OF THE WORK. DAMAGE SHALL INCLUDE BUT NOT BE LIMITED TO DESTRUCTION OR DISPOSAL OF ITEMS INTENDED TO REMAIN OR TO BE SALVAGED.

3. THE ELECTRICAL CONTRACTOR SHALL DE-ENERGIZE AND REMOVE ALL CONDUCTORS AND RACEWAYS TO THEIR POINTS OF ORIGIN WITHIN THE AREA OF DEMOLITION SCOPE. ITEMS IDENTIFIED FOR DEMOLITION SHALL NOT BE ABANDONED IN PLACE. RACEWAYS THAT ENTER MASONRY WALLS AND FLOORS SHALL BE CUT FLUSH AT THE SURFACE FOR PATCHING BY OTHERS. ALL CIRCUIT BREAKERS ASSOCIATED WITH THE DEMOLITION SCOPE SHALL BE DE-ENERGIZED AND LABELED SPARE.

4. ALL REMOVED ITEMS SHALL BE LEGALLY DISPOSED OF UNLESS IDENTIFIED FOR REUSE. THE OWNER'S REPRESENTATIVE SHALL INSPECT ALL RETAINED ITEMS PRIOR TO PLACEMENT IN THE IDENTIFIED STORAGE LOCATION BY THE ELECTRICAL CONTRACTOR.

5. REMOVED FLUORESCENT AND HID LAMPS AND BATTERIES SHALL BE RECYCLED BY A FACILITY APPROVED BY THE OWNER'S REPRESENTATIVE. A UNIFORM HAZARDOUS WASTE MANIFEST SHALL BE PREPARED FOR ALL DISPOSALS AND RETURNED WITH ALL APPLICABLE SIGN OFF'S PRIOR TO APPLICATION FOR FINAL PAYMENT.

## ABBREVIATIONS

A/AMP	AMPERE	IMC	INTERMEDIATE METALLIC CONDUIT
AC	ALTERNATING CURRENT	JB	JUNCTION BOX
AT	AMPERE FRAME	KVA	KILOVOLT-AMPERE
AFF	ABOVE FINISHED FLOOR	KW	KILOWATT
AGF	ABOVE GRADED FLOOR	LTC	LIGHTING
AIC	AMPERE INTERRUPTING CAPACITY	PWR	POWER
AL	ALUMINUM	MCB	MAIN CIRCUIT BREAKER
AT	AMPERE TRIP	MEC	MASSACHUSETTS ELECTRICAL CODE
ATS	AUTOMATIC TRANSFER SWITCH	MLO	MOUNTED LUGS ONLY
AWG	AMERICAN WIRE GAUGE	MTC	MOUNTED
C	CONDUIT	MCC	MOTOR CONTROL CENTER
CKT	CIRCUIT	NEC	NATIONAL ELECTRICAL CODE
CB	CIRCUIT BREAKER	NS	NON-SYSTEM
CU	COPPER	NTS	NOT TO SCALE
CL	CENTERLINE	No., #	NUMBER
DC	DC CURRENT	PC	PLUMBING CONTRACTOR
DE	DUAL ELEMENT	RPM	REVOLUTIONS PER MINUTE
DWG	DRAWING	RMS	ROOT MEAN SQUARE VALUE
EC	ELECTRICAL CONTRACTOR	RGS	RIGID STEEL CONDUIT
EMH	ELECTRICAL MANHOLE	SF	SQUARE FOOT
EWC	ELECTRICAL WATER COOLER	SN	SOLID NEUTRAL
EMT	ELECTRICAL METALLIC CONDUIT	ST	SPLIT-TRIP CIRCUIT BREAKER
FMT	FLAME LIQUID TIGHT METALLIC TUBING	SWBD	SWITCHBOARD
CC	GENERAL CONTRACTOR	TYP	TYPICAL
GND	GROUND	V	VOLTS
GF	GROUND FAULT CIRCUIT BREAKER	VA	VOLT-AMPERE
GFI	GROUND FAULT INTERRUPTING	VFD	VARIABLE FREQUENCY DRIVE
HVAC	HEATING, VENTILATION AND AIR CONDITIONING	WP	WEATHERPROOF
HP	HORSEPOWER		

## EXISTING EQUIPMENT DESIGNATIONS

X EXISTING TO BE REMOVED. REMOVE ALL ASSOCIATED CONDUIT AND CONDUCTORS.

XM EXISTING TO REMAIN.

XN EXISTING EQUIPMENT TO BE REPLACED WITH NEW. CONNECT NEW EQUIPMENT TO EXISTING CIRCUIT.

XR EXISTING EQUIPMENT TO BE RELOCATED. JUNCTION AND EXTEND EXISTING CONDUIT AND CONDUCTORS.

XL NEW LOCATION FOR EXISTING EQUIPMENT. JUNCTION AND EXTEND CONDUIT AND CONDUCTORS AS REQUIRED.

LIGHTING FIXTURE SCHEDULE					
Fixture Type	Description	Manufacturer and Catalog Number	Lamps		Voltage
			No.	Wattage	
	LED EMERGENCY BATTERY UNIT WITH HEADS	PHILIPS CHLORIDE S2-50L-M7-W-IC-T	2	14	LED
	LED INTERIOR EMERGENCY REMOTE HEADS	PHILIPS CHLORIDE SR2M7FW	2	14	LED
	LED EXTERIOR EMERGENCY REMOTE HEADS	PHILIPS CHLORIDE VLL2R0	2	14	LED
	LED EXIT SIGN, SINGLE FACE, BATTERY BACK-UP, CEILING OR WALL MOUNTED	PHILIPS CHLORIDE CXL-3-R-W	-	4	LED

# TURNER GROUP

The H.L. Turner Group Inc.

27 Locke Rd.  
Concord, New Hampshire 03301  
t:603.228.1222  
hltturner.com

COPYRIGHT - THE H.L. TURNER GROUP INC. 2018  
(C) Electronic images of these documents may be used for the purpose of expediting shop drawings and coordination drawings for the project only - except as noted above. The documents are the property of the architect and may not be used to use them for any other purpose. The Architects or Engineers shall not appear on any documents that are modified by others. The Architect shall bear no responsibility for any modifications to the original documents by others.



BLW Engineers, Inc.

311 Great Road, Post Office Box 1551  
Littleton, Massachusetts 01460  
T: 978.486.4301 F: 978.428.0067  
www.blwengineers.com


HVAC \* ELECTRICAL \* PLUMBING \* FIRE PROTECTION

KEY PLAN:  
PROJECT TITLE/ ADDRESS:  
**EMERGENCY LIGHTING  
UPGRADES**  
TOWN OF SALEM, NH

SALEM DISTRICT COURT  
35 GEREMONTY DR  
SALEM, NH


ISSUE:  
BID SET  
09/20/2018

PROJ. NO.: 18104 STAMP  
SCALE:  
DES. BY: SWD  
DRAWN BY: SWD  
CHKD BY: JP  
ISSUE DATE: 09/20/2018  
REVISIONS



SHEET TITLE:  
**ELECTRICAL  
DEMOLITION  
BASEMENT PLAN**

**ED1.1**



# TURNER GROUP

The H.L. Turner Group Inc.

27 Locke Rd.  
Concord, New Hampshire 03301  
t:603.228.1122  
hltturner.com

COPYRIGHT - THE H.L. TURNER GROUP INC. 2018  
(C) Electronic images of these documents may be used for the purpose of expediting shop drawings and coordination drawings for this project only - except as noted above. The documents are the property of the architect and may not be used to any other purpose. The architect or engineer's seal shall not appear on any documents that are modified by others. The architect shall bear no responsibility for any modifications to the original documents by others.



BLW Engineers, Inc.

311 Great Road, Post Office Box 1551  
Littleton, Massachusetts 01460  
T: 978.486.4301 F: 978.428.0067  
www.blwengineers.com

HVAC \* ELECTRICAL \* PLUMBING \* FIRE PROTECTION


KEY PLAN:  
PROJECT TITLE/ ADDRESS:  
**EMERGENCY LIGHTING  
UPGRADES**

TOWN OF SALEM, NH

SALEM DISTRICT COURT  
35 GEREMONTY DR  
SALEM, NH


ISSUE:  
BID SET  
09/20/2018

PROJ. NO.: 18104 STAMP  
SCALE:  
DES. BY: SWD  
DRAWN BY: SWD  
CHKD BY: JP  
ISSUE DATE: 09/20/2018  
REVISIONS



SHEET TITLE:  
**ELECTRICAL  
DEMOLITION  
FIRST FLOOR PLAN**

**ED1.2**



# TURNER GROUP

The H.L. Turner Group Inc.

27 Locke Rd.  
Concord, New Hampshire 03301  
t:603.228.1122  
hltturner.com

COPYRIGHT - THE H.L. TURNER GROUP INC. 2018  
(C) Electronic images of these documents may be used for the purpose of expediting shop drawings and coordination drawings for this project only - except as specifically noted. These documents are the property of the architect and may not be used for any other purpose. The architect or engineer shall not appear on any documents that are modified by others. The architect shall bear no responsibility for any modifications to the original documents by others.



BLW Engineers, Inc.

311 Great Road, Post Office Box 1551  
Littleton, Massachusetts 01460  
T: 978.486.4301 F: 978.428.0067  
www.blwengineers.com

HVAC \* ELECTRICAL \* PLUMBING \* FIRE PROTECTION

KEY PLAN:  
PROJECT TITLE/ ADDRESS:  
**EMERGENCY LIGHTING  
UPGRADES**


TOWN OF SALEM, NH

SALEM DISTRICT COURT  
35 GEREMONTY DR  
SALEM, NH

ISSUE:


BID SET  
09/20/2018

PROJ. NO.:	18104	STAMP
SCALE:		
DES. BY:	SWD	
DRAWN BY:	SWD	
CHKD BY:	JP	
ISSUE DATE:	09/20/2018	
REVISIONS		



SHEET TITLE:  
**ELECTRICAL  
BASEMENT PLAN**

**E1.1**



# TURNER GROUP

The H.L. Turner Group Inc.

27 Locke Rd.  
Concord, New Hampshire 03301  
t:603.228.1122  
hltturner.com

COPYRIGHT - THE H.L. TURNER GROUP INC. 2018  
(C) Electronic images of these documents may be used for the purpose of expediting shop drawings and coordination drawings for this project only - except as noted above. The documents are the property of the architect and may not be used to use them for any other purpose. The Architects or Engineers shall not appear on any documents that are modified by others. The Architect shall bear no responsibility for any modifications to the original documents by others.



BLW Engineers, Inc.

311 Great Road, Post Office Box 1551  
Littleton, Massachusetts 01460  
T: 978.486.4301 F: 978.428.0067  
www.blwengineers.com

HVAC \* ELECTRICAL \* PLUMBING \* FIRE PROTECTION

KEY PLAN:  
PROJECT TITLE / ADDRESS:  
**EMERGENCY LIGHTING  
UPGRADES**


TOWN OF SALEM, NH

SALEM DISTRICT COURT  
35 GEREMONTY DR  
SALEM, NH

ISSUE:

BID SET  
09/20/2018

PROJ. NO.:	18104	STAMP
SCALE:		
DES. BY:	SWD	
DRAWN BY:	SWD	
CHKD BY:	JP	
ISSUE DATE:	09/20/2018	
REVISIONS		



SHEET TITLE:  
**ELECTRICAL  
FIRST FLOOR PLAN**

**E1.2**

